



Capitol Cement
 11551 Nacogdoches Rd.
 San Antonio, Texas

Masonry Cement N C 91

Date : April 11, 2024

Production Period:

Beginning 2/1/2024
 Ending 2/29/2024

PHYSICAL

Item	Spec. Limit	Test Results
Air Content of Mortar (volume %)	8.0 minimum 21.0 maximum	15
Retained on 325 mesh sieve (%)	24 maximum	1.20
Water retention (%)	70 minimum	84
Time of Setting (minutes) Gillmore		
Initial Not less than	120	160
Final Not more than	1000	300
Compressive Strength		
7 Day (psi)	500 minimum	2460
28 Day (psi)	900 minimum (Feb)	2765

We certify that the above cement, at the time of shipment meets the chemical and physical requirements of the current ASTM C 91 specifications. The above data represents the averages of representative samples from production.

Signature 
 Douglas Conroy

Title Chief Chemist