



Capitol Cement
 11551 Nacogdoches Rd.
 San Antonio, TX 78217

Masonry Cement N - C 91

Date: April 9, 2026

Production Period:

Beginning February 1, 2026

Ending February 28, 2026

PHYSICAL

Item	Spec. Limit	Test Result
Air Content of Mortar (volume %)	8.0 minimum 21.0 maximum	<u>14</u>
325 % retained	24 maximum	<u>0.90</u>
Water Retention (%)	70 minimum	<u>90</u>
Time of setting (minutes)		
Gilmore		
Initial	Not less than 120	<u>285</u>
Final	Not more than 1000	<u>390</u>
Compressive Strength		
7 Day (psi)	500 minimum	<u>2280</u>
28 Day (psi) (Jan)	900 minimum	<u>3010</u>

We certify that the above cement, at the time of shipment meets the chemical and physical requirements of the current ASTM C 91 specifications. The above data represents the averages of representative samples from production.


 Violeta Vega-Gomez, Quality Control Manager