



Capitol Cement
 11551 Nacogdoches Rd.
 San Antonio, TX 78217

ECO-MENT SPEC® Type I L (10)

Date: May 11, 2026

Production Period:

Beginning April 1, 2026

Ending April 30, 2026

CHEMICAL			PHYSICAL		
Item	Spec. Limit	Test Result	Item	Spec. Limit	Test Result
SiO ₂ (%)		<u>19.2</u>	Air Content of Mortar (volume %)	<i>12 max</i>	<u>5.5</u>
Al ₂ O ₃ (%)		<u>5.1</u>	Blaine Fineness (m ² /kg)	A	<u>443</u>
Fe ₂ O ₃ (%)		<u>2.5</u>	ASTM C1038	<i>0.020%</i>	<u>0.007</u>
CaO (%)		<u>66</u>	Density		<u>3.02</u>
MgO (%)		<u>0.9</u>	Time of Setting (minutes)		
SO ₃ (%)	<i>3.0% max (b)</i>	<u>4.0</u>	Vicat, Initial	<i>Not less than 45</i>	<u>112</u>
Na ₂ O (%)	A	<u>0.10</u>	Vicat, Final	<i>Not more than 420</i>	<u>294</u>
K ₂ O (%)	A	<u>0.53</u>	Compressive Strength		
Equivalent alkalis (%)	C	<u>0.45</u>	1 Day (psi)	A	<u>2,270</u>
	<i>minimum</i>	<u>0.42</u>	3 Day (psi)	<i>minimum (1890)</i>	<u>4,200</u>
	<i>maximum</i>	<u>0.47</u>	7 Day (psi)	<i>minimum (2900)</i>	<u>4,960</u>
Ignition Loss (%)	<i>10% max</i>	<u>6.2</u>	28 Day (psi) (Mar)	<i>minimum (3620)</i>	<u>6,530</u>
Class F Fly Ash (%)		<u> </u>			
CaO % in Ash	A	<u> </u>			
Pumicite (%)		<u> </u>			
Limestone (%)	<i>10% +/- 2.5%</i>	<u>10.25</u>			
CO ₂ (%)		<u>4.36</u>			
CaCO ₃ in Limestone (%)		<u>97</u>			

(A) Not Applicable; (b) It is permissible to exceed the limit for SO₃, provided it has been demonstrated by Test Method C-1038 that the cement will not develop expansion exceeding 0.020% at 14 days. (C) Reported equivalent alkalis are of the finished cement.

We certify that the above cement, at the time of shipment meets the chemical and physical requirements of the current ASTM C 595, C 1012, C 227 specifications. The above data represents the averages of representative samples from production.



Capitol Cement
11551 Nacogdoches Rd.
San Antonio, TX 78217

ECO-MENT SPEC® Type I L (10)

Date: May 11, 2026

Production Period:

Beginning April 1, 2026

Ending April 30, 2026

A handwritten signature in black ink, appearing to read 'V. Vega-Gomez', is written over a horizontal line.

Violeta Vega-Gomez, Quality Control Manager